





ASX/Media Release – 08 August 2017

Orinoco Completes Low-Capital Cost Modifications to Cascavel Process Plant Ahead of Restart

Key Points:

- Low capital cost process plant modifications completed.
- 500-tonne trial parcel successfully processed.
- Improved Particle Size Distribution achieved.
- Sluice Box recovering gold otherwise lost to tailings.
- Processing operations set to restart later this quarter.

Orinoco Gold Limited (ASX: OGX) (**Orinoco** or **Company**) is pleased to advise that it has completed the previously announced low capital cost modifications to the processing plant at the Cascavel Gold Mine (**Cascavel**). A 500-tonne trial parcel of low-grade ore has been successfully processed to assess the impacts of the modifications, with positive results.

Modifications completed

The modifications completed consisted of:

- Replacement of screen deck panels with smaller aperture panels; and
- Fabrication and installation of a Sluice Box.

In addition, the primary and secondary crusher jaw gaps were reduced.

Replacement of Screen Deck Panels

The two (2) panel screen deck used during processing operations in 2016 was equipped with:

- An upper deck screen panel with 8.0mm x 25.5mm apertures; and
- A lower deck screen panel with 1.6mm x 12.4mm apertures.

As demonstrated by the Hazen testwork (see Figure 1 below and ASX announcement dated 01 June 2017), a smaller particle size distribution (**PSD**) results in improved gold recovery.

In line with the advice received from the Company's metallurgical consultant, Mining Plus, the panels on both the upper and lower screen decks were changed out for smaller aperture panels with the aim of producing a finer product, with an improved PSD, to the gravity recovery circuit.



The change-out occurred in two (2) phases:

- The upper screen deck panel was changed to a 5mm small dimension in June; and
- The lower screen deck panel was changed to 1.2mm small dimension in July.





Figure 1: Cumulative Gold Recovery as a Function of Grind Size


Fabrication and Installation of Sluice Box

In line with the advice received from the Company's metallurgical consultant, Mining Plus, a sluice box was fabricated and installed (see Pictures 1 and Picture 2) into the Knelson concentrator tailings line as a final capture point for any gold prior to the tailings being discharged to the dewatering biers.



Picture 1: Sluice Box Installed





Picture 2: Sluice Box in operation

500-tonne trial parcel

A 500-tonne trial parcel of low-grade (\approx 1.0 g/t Au) ore was processed in late June/early July to assess the impact of the modifications made.

Results of Trial

The purpose of the modifications was to lower the tail grade (and hence improve overall gold recovery) by a combination of reducing the PSD being fed to the gravity circuit and capturing gold from what was previously the final tailings stream.

Particle Size Distribution

As noted above, the change-out of the screen deck panels occurred in two phases with the upper screen deck being changed out in June and the lower screen deck being changed out in July. As can be seen from Figure 2 below, the impact of both change-outs resulted in a reduction in the PSD to the gravity circuit when compared to the 2016 (August shown) PSD.





Figure 1: PSD of Gravity Circuit Feed

One noted downside of the reduced PSD for July was that the recirculating load to the Vertical Shaft Impactor (VSI) tertiary crushing unit increased, which necessitated the throughput rate of the processing plant being reduced to 12 tonnes per hour (tph) from its nominal design throughput rate of 15tph.

With the focus for the mining team changing from tonnes mined to grade mined (i.e. the target is to have lower tonnes but at a higher grade for the same ounces), this slight reduction in throughput rate is not considered to be material and is likely to be minimised as more experience is gained by the processing team in operating the process plant under the new set-up.

Mining Plus is also reviewing the applicability of using a combination of the 1.6mm and 1.2mm panels for the lower screen deck to bring the throughput rate back to the 15tph nominal target.

Sluice Box

The sluice box is a passive gold capture device which is operated with minimal operating costs. In the course of processing the trial parcel of ore, a number of small modifications were made to the sluice box to improve its performance. During the processing of the trial parcel of ore, the sluice box recovered approximately 10 grams of gold which would otherwise have been "lost" to the tailings. This represents an improvement in overall gold recovery of approximately 2%.

Trial Results

Ore	Reconciled	Reconciled	Gravity	Sluice Box	Total
Processed	Head Grade	Tail Grade	Circuit	Recovery	Recovery
			Recovery		
504.4 tonnes	0.98 g/t Au	0.26 g/t Au	353.92 g Au	10.08 g Au	364 g Au
			71.5%	2.0%	73.5%



Orinoco's Chief Executive Officer, Mr Craig Dawson, said both of the low-cost plant modifications recommended by the Company's consultants had been successfully implemented, with positive results.

"Both modifications have delivered the desired outcome and resulted in an overall reduction in the tail grade, and hence improved recovery, from the process plant. Further improvements are anticipated as the operating parameters of the plant are modified once processing operations recommence in earnest later this quarter."

-ENDS-

For further information, please contact:

Craig Dawson Chief Executive Officer Orinoco Gold Limited 08 9482 0540 info@orinocogold.com Nicholas Read Managing Director Read Corporate 08 9388 1474

Forward-Looking Statements:

This Announcement includes "forward-looking statements" as that term within the meaning of securities laws of applicable jurisdictions. Forward-looking statements involve known and unknown risks, uncertainties and other factors that are in some cases beyond Orinoco Gold Limited's control. These forward-looking statements include, but are not limited to, all statements other than statements of historical facts contained in this presentation, including, without limitation, those regarding Orinoco Gold Limited's future expectations. Readers can identify forward-looking statements by terminology such as "aim," "anticipate," "assume," "believe," "continue," "could," "estimate," "expect," "forecast," "intend," "may," "plan," "potential," "predict," "project," "risk," "should," "will" or "would" and other similar expressions. Risks, uncertainties and other factors may cause Orinoco Gold Limited's actual results, performance, production or achievements to differ materially from those expressed or implied by the forward-looking statements (and from past results, performance or achievements). These factors include, but are not limited to, the failure to complete and commission the mine facilities, processing plant and related infrastructure in the time frame and within estimated costs currently planned; variations in global demand and price for gold materials; fluctuations in exchange rates between the U.S. Dollar, the Brazilian Real and the Australian dollar; the failure of Orinoco Gold Limited's suppliers, service providers and partners to fulfil their obligations under construction, supply and other agreements; unforeseen geological, physical or meteorological conditions, natural disasters or cyclones; changes in the regulatory environment, industrial disputes, labour shortages, political and other factors; the inability to obtain additional financing, if required, on commercially suitable terms; and global and regional economic conditions. Readers are cautioned not to place undue reliance on forward-looking statements. The information concerning possible production in this announcement is not intended to be a forecast. They are internally generated goals set by the board of directors of Orinoco Gold Limited. The ability of the company to achieve any targets will be largely determined by the company's ability to secure adequate funding, implement mining plans and resolve logistical issues associated with mining. Although Orinoco Gold Limited believes that its expectations reflected in these forward-looking statements are reasonable, such statements involve risks and uncertainties and no assurance can be given that actual results will be consistent with these forwardlooking statements. No JORC Mineral Resources or Reserves have been estimated for the Cascavel Gold Mine.