

ASX Announcement

Thursday, 10th September, 2015

European Wave & Tidal Conference Presentations

ASX listed (ASX:CWE) wave technology developer, Carnegie Wave Energy is pleased to inform that it was selected to deliver two presentations this week at the European Wave and Tidal Energy Conference (EWTEC) in Nantes, France. The presentations were delivered by Carnegie's Chief Technology Officer, Jonathan Fiévez, and Carnegie's UK CEO, Tim Sawyer. EWTEC is premier technical and scientific conference on wave and tidal energy globally. A combined version of the presentations is attached and the full EWTEC program is available [here](#).

For more information:

Dr Michael Ottaviano


Managing Director

Carnegie Wave Energy Limited

(08) 9486 4466

enquiries@carnegiewave.com

Website: www.carnegiewave.com



Carnegie Wave Energy Update & Lessons Learned

8th September, 2015

Jonathan Fiévez
Chief Technology Officer



Disclaimer

The information contained herein has been prepared solely for informational purposes and is not an offer to buy or sell or a solicitation of any offer to buy or sell any security or to participate in any trading strategy or to enter into any transaction. If any offer of securities is made, it shall be made pursuant to a definitive offering memorandum prepared by or on behalf of any fund or other issuer which would contain material information not contained herein and which would supersede this information in its entirety.



Carnegie Overview

- Owner and developer of “CETO” wave energy technology
- 46 engineering, commercial, administration staff
- ASX listed, based in Fremantle, Western Australia
- 120 Patents or patents pending globally
- \$100m spent to date on CETO
- 100% owned subsidiaries in the UK, Ireland and Chile



Perth Wave Energy Project – aims & objectives

- Demonstrate CETO 5 technology including:
 - Multiple WECs
 - Power delivery to grid
 - Wave powered reverse osmosis desalination
 - <1 day CETO WEC installation
- 2014 commissioning
- 12 months operation




Perth Wave Energy Project - formation

- Funding secured for 3 Unit project ~\$30m
 - \$22m in Government grant funding
 - Carnegie equity (shareholders)
- Power & Water Offtake to Australian Department of Defence (HMAS Stirling)
- Project team formed
- Approvals received




CETO Fundamentals


Waves driving buoy downward
– hydraulics assisting



Waves and buoyancy pulling buoy
upward – hydraulics resisting





CETO 5 System Architecture



Perth Wave Energy Project – system design

- System design conducted in accordance with Systems Engineering principles
- Modelling techniques developed by Carnegie
- Simulations determined load cases and design limits



Perth Wave Energy Project – CETO WECs

- Designed in-house by Carnegie engineers
- Fabrication and logistics managed by Carnegie engineers and project team



Perth Wave Energy Project – infrastructure

- Pile foundation contract managed by Carnegie Project Team
- Pipe and data cable installation contract managed by Carnegie Offshore Team




Perth Wave Energy Project – WEC installation

- 1st WEC install required 3 days
- 2nd & 3rd WEC installations completed in 1 day
- Retrievals completed in 2 days
- 6 separate WEC install/recovery operations
- Validation of “hot swap” methodology





Perth Wave Energy Project - operation

- > 13,500 hours of cumulative operation
- Exporting power to grid and production of desalinated water
- Range of sea states experienced up to ~6m Hmax
- Regular inspection and maintenance
- >600 GB of data captured



Lessons Learned – overview

- Formal lessons learned process followed shortly after commissioning
- Survey conducted with entire Carnegie team
- Over 600 line items analysed
- Very even split between bodies of knowledge (BOKs)
- Continuous Improvement Programme (CIP) now in service to capture lessons learned





Lessons Learned #1 - value of multiple WECs

- Having multiple WECs was beneficial
- The inherent redundancy offered:
 - Faster time to 'first power' since working components could be robbed from other WECs
 - Some components only testable in-service so subsequent WECs were able to be upgraded with improvements
 - More uptime of the Onshore Plant
- Learnings were transferable with staggered deployment
- Multiple WECs gave more data statistical certainty. Important if data is limited by faults, etc.



Lessons Learned #2 - design for construction early

- Early design work on logistics and WEC installation/recovery resulted in:
 - Simpler procedures
 - Reduced costs for offshore work
 - Reduced risk due to reduced reliance on people/divers
 - Shorter activity durations minimising weather window issues
- In cases where 'constructability' was missed, difficulties ensued
- Ensure early design is developed into detailed procedures



WORKS PROCEDURE - UNIT INSTALLATION


Item	Description	Reference	Complete
234.	Diver disconnects winch omblines, (3 hydraulic and 3 electrical), replacing dummy plugs and cable tags, then releases safety catches.		
235.	Tripode recovers winch umbilical on to ISV retrieving the floats and is hoisted in.		

10.33. Recover BA Holdback Airbags – Demobilisation (NL/AM)

Operational Summary:

- Recover holdback airbags

Item	Description	Reference	Complete
236.	Diver observes BA motion before approaching.		
237.	Diver attaches end of a line from the ISV on to the wrapping of the BA holdback airbag.		
238.	Diver cuts holdback line through the choke/ding where it meets the attached sling, then removes the choke/ding from BA tow point.		




INSTALLATION - Issued 28/06/2015 15:38

CONFIDENTIAL - COMMERCIAL IN CONFIDENCE
THIS DOCUMENT IS UNCONTROLLED WHEN PRINTED.

Page 53 of 71


Lessons Learned #3 - recruit dedicated operators

- Wave energy demonstration plants require 24/7 attention
- Initial reliance on engineers and project staff to be plant operators who were tired from commissioning
- Graduate and undergraduate engineers and scientist now trained as operators
- Very good performance and attention to technical detail from operators
- Presents pool of talent for potential engineering positions




Lesson learned #4 - manage contamination carefully

- System cleanliness extremely important for reliability of plant
- Several components susceptible to failure
- Failures due to contamination can lead to further contamination
- Cleanliness important on a micro and macro level
- CANNOT assume suppliers will deliver clean equipment
- CANNOT assume flushing of assembled system will remove contamination entirely
- Mitigation strategies only as good as initial fluid cleanliness




Research – key activities

- Significant internal research on system control and hydrodynamics
- External research includes:
 - foundation design with UWA using centrifuge to characterise pile performance and novel non-pile solutions
 - Optimal controller research underway with University of Adelaide
 - High reliability PTO with WavePOD consortium (Carnegie, Aquamarine, Bosch Rexroth) in Scotland



Wave Tank Testing – CETO 6 design development


- FloWave Ocean Energy Testing Facility, Edinburgh
- Objectives:
 - Understand the performance of CETO 6 under a range of operational conditions
 - Measure loads under very high energy conditions
 - Validate Carnegie's numerical modelling
- Results showed excellent agreement with numerical modelling, including power output and improved performance through advanced tuning



CETO 6 - next generation

- 1MW capacity target
- 4 x increase in rated capacity vs CETO 5 → ~50% increase in diameter
- On board power generation
- First commercial production design
- CETO 6 Demonstration Project:
 - Garden Island, Western Australia
 - Design start: 2014
 - Project construction: 2016
 - Project commissioning: 2017





Environmental Management & Monitoring

The Perth Wave Energy Project

EWTEC 2015

8 September 2015

Tim Sawyer &
Edwina Davies Ward



Disclaimer


The information contained herein has been prepared solely for informational purposes and is not an offer to buy or sell or a solicitation of any offer to buy or sell any security or to participate in any trading strategy or to enter into any transaction. If any offer of securities is made, it shall be made pursuant to a definitive offering memorandum prepared by or on behalf of any fund or other issuer which would contain material information not contained herein and which would supersede this information in its entirety.

Perth Wave Energy Project (PWEP)

- Garden Island, Western Australia
- 3 x CETO 5 units
- Onshore power plant, reverse osmosis desalination and grid connection
- Power & Water Offtake to Australian Department of Defence (HMAS Stirling)
- Unique test bed globally for monitoring environmental impacts of WEC arrays



PWEP Legislative Framework: Multiple Jurisdictions



PWEP Terrestrial & Marine Environment



Heritage values of Garden Island, Western Australia (Department of Defence 2011)


PWEP Environmental Management

- Early and ongoing consultation
- Leveraging international experience
- Working alongside engineers to improve design & delivery
- Comprehensive EIA and effective management measures
- Overall, PWEP assessed with no high or unacceptable risks or potential impacts after management



PWEP Environmental Monitoring & Assessment

- Collaborative approach
- Ongoing monitoring and assessment:
 - Underwater noise
 - Sediment & water quality
 - Coastline impacts
 - Impact on sea users, flora & fauna



PWEP Environmental Monitoring & Assessment



Revegetation
June 2014




Revegetation
June 2015

PWEP Operations


- 3 units, > 13,500 hours of cumulative operation
- Exporting power to grid
- Range of sea states experienced
- Regular inspection and maintenance
- CETO unit and system performance in line with expectations
- Proven deployment and retrieval capability
- Within consent conditions and in accordance with our comprehensive Environmental Management System.



-
- A 3D visualization of the Ristretto site area. The terrain is shown in shades of green and blue, indicating elevation. A red line represents the proposed cable route, which runs diagonally across the image. A specific point on this route is labeled 'KP7.5' in a red box. Another label 'Scarp KP7.515' with a height of 3 m and a slope of 16° points to a specific feature on the terrain. A north arrow is visible in the top right corner.



Upcoming Milestones



2014:

- ✓ Construction of the Perth Project
- ✓ CETO 6 Project design and funding

2015:

- ✓ Perth Project grid connection & operation
- ✓ 13,500+ hours cumulative operation
- CETO 6 Project development

2016/17:

- Construction of CETO 6 Project in Australia
- Development and construction of CETO 6 Project in the UK

CETO Development Pathway



Demonstration Projects



Commercial Projects

